



**Dr. A. P. J. Abdul Kalam IIIT-ONGOLE  
RGUKT,A.P**

Camp Office: RK Valley (Idupulapaya), Vempalli (M), Y.S.R. (Dist.) A.P – 516330

Mail Id:spc.ong@rgukt.in

**Ref No: RGUKT/ONG/Proc/ Concrete Flooring/2020**

**Date: 22-06-2020**

**NOTICE INVITING QUOTATIONS**

Dr. A. P. J. Abdul Kalam IIIT-ONGOLE, RGUKT,AP invites sealed quotations from interested parties to execute Concrete Flooring and Repair Works for Dr. A. P. J. Abdul Kalam IIIT-ONGOLE campus, RGUKT,A.P, located at Idupulapaya, Vempalli, YSR Dist.

**Last Date for Submission : 29-06-2020**

**Item Description : As per Annexure – A & B**

**Address for Communication: Coordinator Stores and Purchases (i/c),**

Dr. A. P. J. Abdul Kalam IIIT-ONGOLE  
RGUKT-AP.  
RK Valley (AP-IIIT),  
Vemaplli Mandal,  
YSR Dist, Andhra Pradesh-516330

**Terms & Conditions:**

1. The bidder should have a registered firm or a registered contractor.
2. The Bidder is required to submit firm's registration certificate or license of contractor.
3. The Bidder should not have been barred by any PSU/Govt. Dept. in doing business with them.
4. The Bidder is required to quote for the complete bill of quantity. Partial quote are liable to be rejected.
5. Bidders are requested to follow the given price bid format to quote the items. The rate for the item may be quoted in INR. The offers should indicate unit price (excluding GST).
6. The quotations must be addressed to "The Director, Dr. A. P. J. Abdul Kalam IIIT-ONGOLE, RGUKT,AP, Camp Office at IIIT-RK Valley, Idupulapaya, Vempalli(Mandal), YSR Dt-516330".
7. The sealed cover should be super scribed with above mentioned Ref. NO and must reach the office on or before the last date through Speed-post/Registered Post/ordinary post.
8. Work should be done within specified days mentioned in Purchase Order,
9. Unloading of items and delivery to the store place shall be responsibility of the firm.
10. Payment shall be made 100% after delivery of the items in good condition.
11. Dr. A. P. J. Abdul Kalam IIIT-ONGOLE, RGUKT, A.P reserves the right to reject any/all quotation(s) without assigning any reasons whatsoever.
12. Quotations received against our notification are considered as accepting the terms and conditions of Dr. A. P. J. Abdul Kalam IIIT-ONGOLE, RGUKT, A.P, RK Valley.

**Sd/-  
Administrative Officer**



**ANNEXURE-B**

<b>REPLACEMENT OF DAMAGED TILES FLOORING WITH CONCRETE FLOORING AT GIRLS DINNING WASH AREA</b>										
<b>S.No</b>	<b>Description</b>	<b>Length</b>	<b>Width</b>	<b>Depth</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>		
<b>1)</b>	Plain cement concrete M7.5 (1:4:8) proposition nominal mix using 40mm size aggregate Including all Material charges & Labor charges									
	outside wash area south side	9.4	1.65	0.1	1.551	cum				
	outside wash area east side	7	1.5	0.1	1.05	cum				
	Girls dining hall drinking water area	10	1.65	0.1	1.65	cum				
	inner wash area south side	10.4	1.5	0.1	1.56	cum				
	inner wash area east side	4.8	1.25	0.1	0.6	cum				
	inner wash area north side	10.4	1.1	0.1	1.144	cum				
					7.555	cum				
<b>2)</b>	Granolithic Concrete flooring 20 mm thick with CC (1:1:2) Using 6mm-12mm size Crushed metal laid over 10mm thick CC flooring Bed (1:4:8) with 40 mm metal Including material labor & all charges.									
	outside wash area south side	9.4	1.65		15.51	sq.mt				
	outside wash area east side	7	1.5		10.5	sq.mt				
	dining hall drinking water area	10	1.65		16.5	sq.mt				
	inner wash area south side	10.4	1.5		15.6	sq.mt				
	inner wash area east side	4.8	1.25		6	sq.mt				
	inner wash area north side	10.4	1.1		11.44	sq.mt				
<b>3)</b>	Removal & disposal of Existing Damaged tiles & Flooring									
	outside wash area south side	9.4	1.65		15.51	sq.mt				
	outside wash area east side	7	1.5		10.5	sq.mt				
	Girls dining hall drinking water area	10	1.65		16.5	sq.mt				
	inner wash area south side	10.4	1.5		15.6	sq.mt				
	inner wash area east side	4.8	1.25		6	sq.mt				
	inner wash area north side	10.4	1.1		11.44	sq.mt				
<b>4)</b>	Removal of jammed Drain Pipes & Replace with new PVC 5" pipe	25.6 running meter line with PVC 5" pipe								
<b>Grand Total</b>										